

Approved by Alger County
Land Survey Re monumentation
Peer Group Under Act 345 of
P.A. of 1990 On JUNE 1994

Arnold Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-227

For corners in

| Alger (County) | Located In: | Corner Code # |
|---------------------------------------|---------------------------|---------------|
| 1. Public Land Survey | T <u>46N</u> R <u>18W</u> | <u>C3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded June 24, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec
on Page 227

Arnold Carlson
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Janros, in a field survey on July 15, 1993, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | ● | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C3: P.L.S., George E. Adair, DS, 1855. Set post at corner of Sections 5, 6, 7 & 8. Sugar 14, N.15 E., 10 links. Y. Birch 13, S.33 W., 58 links. C.C.I. Co., Forestry Division, On land & Timber Examination Report as 'Iron' and 'Iron Pipe', later reports as 'Brass Cap', 1946 through present. Glenn A. Bergey, RLS, 1974, Found original BT and monumented with Brass capped monument. Recorded in corner record No. 57, A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C3: Found 6 inch square concrete monument with 3 1/4 inch brass cap. Stamped P.A. 345 in. cap to identify it's perpetuation. Original Y. Birch BT in southwest position still standing and growing with scribe marks still visible. Renewed existing reference trees and survey marker signs. Monument is in excellent condition, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C3: Stamped PA345 in brass cap of conc. mon., mon. is in sound condition. Renewed exist reference trees w/BT signs, blazed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Exist - Hemlock 12", S.54 E., 22.05 feet. Exist - Hemlock 11", N.03 E., 64.90 feet. Exist - Beech 20", S.63 W., 54.15 feet. Exist G.L.O. original BT, Y. Birch 26", S.30 W., 38.3 feet. Sur. Sign post North, 0.9 feet. Sur. Sign post N.W.

Signed by Robert L. Janros
Surveyor's Michigan License No. 25849

Date 1 June, 1994