

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On JUNE 19 94

Merald W. Carlson  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

4-228

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 18W	C4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded June 24, 1994  
at 8:00 o'clock A. M., and  
Recorded in Liber 4 of Corner Rec  
on Page 228

DuP. W. Kinnaman  
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on September 24, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		●		8		9		10		11		12
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C4: P.L.S., George E. Adair, DS, 1855. Set quarter section post. Beech 5, N.37 W., 45 links. Beech 5, S.47 E., 44 links. C.C.I. Co., Forestry Division, on Land & Timber Examination Report as "Iron", 1946 through present. Robert L. Jamros, RLS, 1988, Found 1 1/2" Iron pipe as part of Section survey, and installed 1/2" x 18" rebar w/RLS cap in center of 1 1/2" iron pipe with top of rebar 0.6 feet above grade. Established new reference objects, Maple 11", S.49 W., 4.62 feet, Maple 9", S.15 E., 17.82 feet, Maple 7", N.53 E., 13.45 feet, Maple 10", N.30 W., 22.06 feet. Record No. 3.339 A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C4: Found 1/2" Rebar with RLS cap identified by recorded reference objects. Installed monument over existing 1/2" rebar. Renewed existing reference trees and installed Survey Marker Sign. Location marks well with BT section corner to South and with section distances, and is accepted as the best available evidence of the position of the original corner. Corner lies in open mixed hardwoods and Southeasterly of existing residence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4: Set 2 1/4" x 30" Alum. Monument w/  
3 1/4" Alum. cap over existing 1/2"  
rebar stamped to I.D. corner position.  
Renewed existing reference trees w/BT  
signs and painted. Set PK nails for  
measuring w/brass I.O. washers in the  
following reference trees. Exist -  
Maple 11", S.49 W., 4.62 feet,  
"1/4S-BT". Exist - Maple 9", S.15 E.,  
17.82 feet, Not Scribed. Exist - Maple  
7", N.53 E., 13.45 feet, "BT". Exist -  
Maple 10", N.30 W., 22.06 feet, "BT".

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 1 June, 1994