

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On JUNE 19 94

Harold Carlson  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

4-229

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	C5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded June 24, 1994  
at 8:00 o'clock A. M., and  
Recorded in Liber 4 of Corner Rec.  
on Page 229

Paul W. Kimmner  
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on September 30, 1993, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C5: P.L.S., George E. Adair, DS, 1855. Set post at corner of Sections 7, 8, 17 & 18. W. Pine 16, N.11 W., 54 links. Spruce 5, S.66 E., 5 links. C.C.I. Co., Forestry Division, on Land & Timber Examination Report as, "Sq. Tan and Iron", 1946 through present.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C5: Began at BT corner, Sections 8, 9, 16 & 17 and ran corrected compass line on G.L.O. Bearing West to corner position noting terrain calls along line. Fir, sugar and beech line tree positions were searched along line with negative results. At approximate Corner location found Sq. Tan post set by C.C.I. Co. Forestry Division, iron not found. Search for original G.L.O. BT's located decayed W.Pine stump in Northwest position, Spruce in Southeast location destroyed by logging skid road. Established temp corner position from W.Pine stump and ran corrected compass line south 4.93 chains to location of W.Pine line tree. Found remains of W.Pine roots in stump hole in dry spruce marsh, and accepted as G.L.O. line tree position. From 1/4 Section corner Sections 7 and 8 ran corrected compass line on G.L.O. Bearing South to temp corner position, position checks very well. Installed monument at corner position. Established new reference trees and installed Survey Marker Sign. Corner lies on Northerly edge of dry Spruce marsh, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C5: Set 2 1/4" x 30" Aluminum Monument  
w 3 1/4" Aluminum cap stamped to I.D.  
corner position. Est. reference trees  
w/BT signs, blazed, scribed and painted.  
Set PK nails for measuring w/brass I.D.  
washers in the following reference  
trees. W. Pine 20", S.50 E., 29.06 feet  
'S17-BT'. W. Pine 14", N.46 E., 18.01  
feet 'S8-BT'. Hemlock 16", N.73 W.,  
33.59 feet 'S7-BT'. W. Pine 22", S.53  
W., 3.89 feet 'S18-BT'. Survey Marker  
Sign, N.87 E., 0.80 feet.

Signed by Robert L. Jamros Date 1 June, 1994

Surveyor's Michigan License No. 25849