

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On JULY 1994

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-230

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>D5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded June 24, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of CORNER Rec.
on Page 230

Gerald W. Carlson
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on October 03, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D5: P.L.S., George E. Adair, DS, 1855. Set quarter section post. W. Pine 11, N.60 E., 40 links. Hemlock 9, S.64 W., 43 links. C.C.I. Co., Forsetry Division, On Land & Timber Examination Report as "4' Tam, Iron, 2' Post and Sq. Spruce Stub", 1946 through present.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D5: Began at BT corner, Sections 8, 9, 16 & 17 and ran a corrected compass line on G.L.O. Bearing west, set temp post at corner position. Continued on corrected compass line on G.L.O. Bearing to corner of Sections 7, 8, 17 & 18 and marked random falling. At temp 1/4 section post corrected position and searched for BT positions. Found remains of Hemlock in stump hole, southwest position and remains of W. Pine stump in northeast position. In marking off corner location from remains of original BT's, found 3 1/2' cedar post down under 6" of muck below 10" of water in open Spruce marsh. At point end of post and location established by original BT remains, installed monument. Corner lies 10 feet North of South edge of wet, open Spruce marsh, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D5: Set 2 1/4" x 30" Aluminum Monument
w 3 1/4" Aluminum cap stamped to I.D.
corner position. Est. reference trees
w/BT signs, blazed, scribed and painted.
Set PK nails for measuring w/brass I.D.
washers in the following reference
trees. Maple 6", S.52 E., 27.50 feet
"1/4S-BT". W. Pine 13", N.63 E., 29.07
feet "1/4S-BT". Maple 10", N.73 W.,
28.61 feet "1/4S-BT". Maple 7", S.42
W., 29.02 feet "1/4S-BT". Survey Marker
sign, N.29 W., 0.90 feet.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 1 June, 1994