

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-2-1995

MAY 10 1995

COMMISSION

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-286

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	E3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
MAY 9:00 a.m.

APR 20 1995

DONALD W. LINDNER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3					●								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on November 07, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E3: PLS-George E. Adair, DS, 1855, Set post corner of sections 4,5,8 and 9, - Y.Birch 10", N.88 E., 39 links, Sugar 24", S.55 W., 34 links. CCI Forestry Division, Land and Timber Examination Report, R.J. Brotherton, RLS, 1940, Iron at corner position., No references given. R.L. Jamros, RLS, 1979, Found 1 1/2" pipe monument w/o cap. References: P.Pole #635, S.15 W., 34.0 ft., Beech 10", N.76 E., 34.7 ft., Maple 12", N.10 W., 42.1 ft., Pine 10", N.33 E., 49.4 ft., Recorded in corner record No. 246, Alger County Records. Gerald W. Carlson, RLS, 1981, Found 2" pipe, References: P.Pole, S.16 W., 33.90 ft., 12" Maple, N.16W., 42.01 ft., 4" Maple, N.23 E., 7.77 ft., 8" Beech, N.70 E., 34.69 ft., Recorded in corner record No. 53, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E3: Found 1 1/2" Iron Pipe at north edge of clearing for east-west overhead electric. Existing BT's are P.pole, Beech, Maple, and Pine (Fir-dead). Corner position was used and accepted in section subdivision survey of Section 4, T.46N., R.18W. A search was made at GLO BT locations, results inconclusive. Installed new monument and established additional reference trees. Accepted existing monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Renewed existing reference trees w/ BT signs and paint. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Maple 16", N.14 1/2 W., 42.00 feet, "Dbl. Blz'd", Ex. Beech 14", N.73 E., 34.73 feet, "Dbl. Blz'd", Maple 5", N.29 E., 30.10 feet, "S4 BT", Maple 8", S.51 W., 111.57 feet, "S8 BT", Steel witness post with Survey marker sign, N.20 W., 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April, 1995