

**SURVEY &
REMONUMENTATION**

MAY 10 1995

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

4-287

Gerald W. Carlson
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>F3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

FILED
ME 9:00 a.m.

APR 20 1995

DONALD W. FINNBERG
REGISTERED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Janros, in a field survey on November 04, 1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F3: PLS-George E. Adair, DS, 1855, Set Qr. Section Post- Sugar 18°, N.22 E., 20 links, Beech 24°, S.11 W., 34 links. Geo. L. Depew, CS, 1916, North one quarter corner of Section 9. In center of road, BT stump on NE., Evidence of Wm. Paquan, Indiantown., No references given., Gerald W. Carlson, RLS, 1981., Corner indicated on Alger County Road Comm. Map. No References given, Found 1 1/2" pipe at intersection of roads to North and East, found 4 feet deep. References: 10" Maple, N.64 W., 29.03 ft., P.Pole, S.62 W., 33.10 ft., 4" Maple, N.06 E., 20.35 ft., 8" Maple, N.67 E., 60.57 ft. Recorded in corner record No. 53, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F3: Found 1 1/2" Iron Pipe with existing BT's of 1981 report still evident. Measurements from corner monument to BT's stated in corner record no. 53 verified corner position. Corner position was used and accepted in section subdivision survey of Section 4, T.46N., R.18W. A search was made at GLO BT locations for original BT's, improvements of area destroyed all evidence. Accepted Iron Pipe as the best available evidence of the position of the original corner. Established additional reference trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap over top of existing 1 1/2" pipe monument. Stamped cap to identify corner position. Renewed existing reference trees w/ BT signs and paint. Used existing nails w/ shiners for measure in the following reference trees. Ex. Maple 12", N.61 W., 28.88 feet, "face Blz.", Ex. Maple 5", N.09 E., 20.30 feet, "face Blz.", Ex. Maple 9", N.70 E., 60.63 feet, "face Blz.", P.Pole, S.60 W., 33.08 feet, "BT", Steel witness post with Survey marker sign, N.77 W., 2.0 feet. All bearings are magnetic.

Signed by Robert L. Janros
Surveyor's Michigan License No. 25849

Date 12 April, 1995