

**SURVEY &
REMONUMENTATION**

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

MAY 10 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

4-288

Merrald W. Carlson
Chairman

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>63</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
APR 9 9:00 a.m.

APR 20 1995

DONALD W. HANCOCK
REGISTERED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on November 07, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G3: PLS-George E. Adair, DS, 1855, Set post corner of sections 3,4,9 and 10, - Sugar 8", N.32 W., 15 links, Sugar 20", S.60 E., 17 links. CCI Forestry Division, Land and Timber Examination Report, R. Radcliffe, RLS, 1950, indicates post at corner position. No references given. R.L. Jamros, RLS, 1979, Found 1" steel bar by persons unknown 0.8 feet below grade. References: Elm 8", N.20W., 49.0 ft., Elm 30", S.20 E., 32.2 ft., Elm 10", N.35 E., 29.4 ft., Maple 4", S.50 W., 24.8 ft., Recorded in corner record No. 248, Alger County Records. G.W. Carlson, RLS, 1981, Found 1" iron peg. References: 3" Maple, N.36 E., 30.40 ft., 4" Maple, S.56 E., 16.79 ft., 10" Maple, South, 29.52 ft., 4" Maple, S.42 W., 24.66 ft., Recorded in corner record No.53 Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G3: Found 1" Iron Bar. In report of R.L. Jamros, 1979, corner position was substantiated by testimony of property owner, Mr. LeVeck. A search was made at GLO BT locations for original BT's, evidence has been lost. Area has been improved with track roads and cultivation. Corner position was used and accepted in section subdivision survey of Section 4, T.46N., R.18W. Installed new monument and established additional reference trees. Corner lies 15 ft. Ely of SE corner of clearing lying btwn. two old track roads. Accepted existing monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. cap over top of existing 1" iron monument. Stamped cap to identify corner position. Renewed existing reference trees w/ BT signs and painted. Set PK nails for measure w/ brass I.D. washer in the following reference trees. Ex. Maple 6", S.55 E., 16.88 feet, "face blz", Ex. Maple 16", S.01 W., 29.52 feet, "face blz", Ex. Maple 7", S.43 W., 24.57 feet, "Dbl Blz", Maple 4", N.37 E., 26.35 feet, "S3 BT", Steel witness post with Survey marker sign, N.60 W., 2.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
Surveyor's Michigan License No. 25849