

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-232

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	<u>67</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded June 24, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Corner Rec.
on Page 232

Donald W. Carlson
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 03, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G7: P.L.S., George E. Adair, DS, 1855. Set post at corner of Sections 15, 16, 21 & 22. B. Ash 6, N.48 E., 22 links. Cedar 7, S.51 W., 17 links. C.C.I. Co. Forestry Division, on Land & Timber Examination Report as 'Iron and Sq. Cedar', 1946 through present, U.S. Forest Service, no records of this corner position on file. Corner noted, with no detail, on M.D.S.H. Construction Plans for State Highway M-28.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G7: Found old 3 inch sq. Cedar Post and a newer 4 inch sq. Cedar Post, no iron found. Two existing NBT were evident but without benefit of necessary information, no records of. Standing close to the two post there is a 10 inch Fir with a yellow rusted, metal U.S.F.S. location tag, U.S.F.S. records show no information for this corner location. Corner checks well with G.L.O. terrain calls, edge of swamp to North and East. Installed monument in place of cedar post and established new reference trees and Survey Marker sign. Corner lies in Cedar and Spruce swamp, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G7: Set 2 1/4" x 30" Alum. monument w/3
1/4" Alum. cap stamped to I.D. corner
position. Est. reference trees w/BT
signs, blazed, scribed and painted. Set
PK nails for measuring w/brass I.D.
washers in the following reference
trees. Black Spruce 14', N.57 E., 26.63
feet, "S15-BT". Cedar 10', S.22 E.,
44.51 feet, "S22-BT". Exist - Fir 8',
N.88 W., 12.91 feet. Black Spruce 13',
N.20 W., 23.64 feet, "S16-BT". Sur.
Marker Sign, N.55 W., 0.90 feet.

Signed by

Robert L. Jamros
25849

Date

1 June, 1994

Surveyor's Michigan License No.