

SURVEY &

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-289

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>46N</u> R <u>18W</u>	H3	SURVEY & REMONUMENTATION <u>MAY 10 1995</u> COMMISSION
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

FILED
9:00 a.m.

APR 20 1995

DONALD W. CARLSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on November 03, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H3: PLS-George E. Adair, DS, 1855, Set Qr. Section Post- Y.Birch 10", N.73 E., 16 links, Sugar 16", S.77 W., 25 links. CCI Forestry Division, Land and Timber Examination Report, R. Radcliffe, RLS, 1950, indicates 4' post at corner. No records filed between 1950 & 1979. William D. Roberts, 1979, on CCI Land Corner Record Reports, Replaced old post with new 4' ironwood post from old NBT's - Witness: Hard Maple 4", S.89 E., 23 links, Hard Maple 10", N.84 W., 27 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H3: Began at corner of Sections 2-3-10-11 and ran corrected compass line on GLO bearing west. At 4.90 chains leave meadow, GLO 5.0 chains, and at 8.59 chains found stump hole with roots and traces of Y.Birch bark around peripheral. GLO line tree 8.62 chains, Y.Birch 12". Continuing west on corrected compass line to 40.01 chains (GLO 39.97 Ch.) and found wood post. A search was made for evidence of GLO BT's, found remains of Y.Birch and traces of bark in stump hole in the GLO N.73 E., 16 links location. From existing post found two existing BT's from 1979 report in good condition. Replaced existing post with new monument and established additional reference trees. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H3: H3: Set 2 1/4" x 30" Alum. Monument w 3 1/4" Alum. Cap stamped to identify corner position. Renewed existing and established reference trees w/ BT signs, blazed, scribed and paint. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Sugar 5", S.88 E., 15.03 feet, "Dbl Blz", Ex. Sugar 13", N.82 W., 17.81 feet, "Dbl Blz", Sugar 7", N.23 E., 40.56 feet, "1/4s BT", Sugar 12", S.06 W., 32.40 feet, "1/4s BT", Steel witness post with Survey marker sign, S.29 E., 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
Surveyor's Michigan License No. 25849