

Approved by Alger County  
 Survey Remonumentation  
 Survey Group Under Act 345 of  
 P.A. of 1930 On 4-8 19 95

Donald W. Carlson  
 Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

4-290

For corners in

Alger  
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 46N R 18W
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

**MAY 10 1995**

**COMMISSION**

FILED  
 APR 9 9:00 a.m.

APR 20 1995

DONALD W. CARLSON  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on November 03, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I3: PLS-George E. Adair, OS, 1855, Set post corner of sections 2,3,10 and 11, - Sugar 13", N.43 E., 34 links, Sugar 8", S.52 1/2 W., 21 links. CCI Forestry Division, Land and Timber Examination Report, R. Radcliffe, RLS, 1950 through 1967 indicates a post and GLO Sugar BT at corner position. No references given., R.L. Jamros, RLS, 1988, Determined corner position by field survey and GLO line tree position. Found 4' post lying down. References: Maple 12", N.05 E., 29.1 ft., Exist. marked "NBT", Cherry 10", N.44 E., 9.8 ft., Maple 12", S.75 W., 30.1 ft., Maple 14", S.06 W., 30.9 ft. Recorded in corner record No. 3-341, Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I3: Found 1" Iron Pipe with RLS cap no. 25849. In report of R.L. Jamros, 1988, corner position was recovered by standard survey methods and GLO line tree position. A search was made at GLO BT locations for original BT's with inconclusive results. Found one remaining reference tree from 1988 report, all others have been cut down. Area logging has been concentrated here recently and in the past. Established additional reference trees. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap over top of existing 1" iron pipe. Stamped cap to identify corner position. Renewed existing and established new reference trees w/ BT signs and paint. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Maple 14", N.11 E., 29.29 feet, "Dbl Blz", Maple 10", S.60 E., 34.94 feet, "S11 BT", Maple 12", S.34 W., 39.65 feet, "S10 BT", Maple 13", N.55 W., 32.71 feet, "S3 BT", Steel witness post with Survey marker sign, N.50 E., 1.7 feet, All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995  
 Surveyor's Michigan License No. 25849