

# SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 245 of  
P.A. of 1990 On 12-10-1997

Donald W. Kinnunen  
Chairman

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-71

For corners in _____ (County)	Located In: _____	Corner Code # _____	
1. Public Land Survey	T <u>46</u> R <u>17</u>	A3	
	T <u>46N</u> R <u>18W</u>	M3	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

FILED  
TIME 8:30 AM

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. James, in a field survey on November 19, 1997, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A3: PLS - William A. Burt, OS, 1841 \* Set post corner of Sections 1 and 12 \* Hemlock 24, S.60 E., 38 links \* White Pine 20, N.39 W., 31 links \*\*\*\*\* William Ives, OS, 1850 \* Hemlock 9, N.42 E., 18 links \* Hemlock 8, S.42 E., 23 links \*\*\*\*\* George L. Depew, County Surveyor, 1915 \* Set standard iron corner from original field notes \*\*\*\*\* J.R. Radcliffe, C.O.I. Co., Forestry Division, 1944 \* Timber cruise sheet indicates brass cap and fences North and East \*\*\*\*\* Frank J. Bray, RLS, Michigan Department of Conservation, 1965 \* Found galv. iron pipe w/3 inch brass cap \* Corner was set by County Surveyor, dated 1915. Checks with several stumps, badly rotten, which possibly were original BT's \* Set witness's - Hemlock 12, S.64 W., 16 links (dead-down, 1997) \* Hemlock 11, N.08 W., 32 links \* Report unrecorded \*\*\*\*\*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A3: Found Alger County Standard Monument w/3 inch brass cap, dated 1915, with 6 inch scribed, squared cedar post and 1 BT of the 1965 unrecorded report. Also found Hemlock 20, w/rusted yellow locator tag \* Corner measures well between section corners North and South \* Renewed exist. BT and established additional reference trees \* Monumented corner position is accepted as a careful and faithful perpetuation of the corner position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A3: Exist. Alger County standard monument w/3 inch brass cap, dated 1915 \* Renewed exist. BT w/BT signs and established additional reference trees w/BT signs, blazed and scribed \* Set PK nails for measure w/Alum, I.C. washers in the following - Exist. BT, Hemlock 16, N.04 W., 21.5 feet, dbl. blzd. \* Hemlock 8, N.49 E., 19.8 feet, "BT" \* Spruce 7, S.51 E., 14.2 feet, "BT" \* Hemlock 6, S.62 W., 27.3 feet, "BT" \* Exist. 6 inch scribed, squared cedar post, Southwest, 0.6 feet \* Exist. yellow, rusted locator tag on a Hemlock 23, S.67 E., 28.5 feet \* All bearings are magnetic.

Signed by Robert L. James  
Surveyor's Michigan License No. 25849

Date 12/18/1997

