

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 545 of
P.A. of 1990 On 12-10-1997

SECTION

05-70

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

(County)

Located In: _____

Corner Code # _____

1. Public Land Survey	T	<u>46</u>	R	<u>17</u>	A 4	
	T	<u>46N</u>	R	<u>10W</u>	<u>M 4</u>	
	T		R			
	T		R			
2. Property Controlling in Section	S		T			
	S		T			
3. Miscellaneous Property in Section	S		T			
	S		T			

FILED
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on November 23, 1997, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

See PLS - William A. Burt, OS, 1841 * Set quarter section post * Sugar 10, S.75 E., 8 links * Sugar 14, N.52 E., 34 links **** Frank L. Bray, RLS, Michigan Department of Conservation, 1965 * Set 1 inch iron pipe w/4 inch Alum. cap * Hard Maple 7, S.15 W., 13 1/2 links * Hard Maple 14, N.03 E., 31 links * Corner was placed on line and midway between section corners to North and to South * Report unrecorded **** Robert L. Jamros, PLS, 1966 * Found galv. iron pipe w/4 inch Alum. cap * Accepted corner monument and established 1 new witness tree * Exist. BT, Maple 15, N.02 E., 21.0 feet * Maple 10, N.58 E., 26.8 feet, blazed, painted and scribed "1/4 67 BT" * Exist. BT, Maple 8, S.20 E., 1.4 feet * Exist. BT, Maple 10, S.18 W., 9.4 feet * Recorded in Liber 3, Page 347, Alger County Corner records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

See Found 1 inch galv. iron pipe w/4 inch Alum. cap and 4 exist. BT's * Corner lies on west toe of slope of small ridge, 100 feet East of small stream * Monumented position lies 0.5 feet South and 0.6 feet East of the midpoint true line position. * Monumented position as set in 1965 was intended to be a thorough and careful survey of the GLO corner position * Property surveys since the 1965 reestablishment of this corner position have accepted and used this monument position * Monumented position of this corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

See Exist. 1 inch iron pipe w/4 inch Alum. cap, stamped to identify corner position * Renewed exist. reference trees w/BT signs * Set 24 nails w/Alum. I.D. washers for measure in the following - Maple 16, N.08 E., 21.00 feet, scribing visible * Maple 12, N.64 E., 26.03 feet, scribing visible * Maple 9, S.20 E., 1.64 feet, scribing visible * Maple 12, S.21 E., 9.03 feet, dbl. blzd. * Survey marker on a first steel post, N.60 E., 1.1 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

