

Herald Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

5-21

For corners in
ALGER
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 21W F1
 T 46N R 21W F13

2. Property Controlling
 in Section

S ___ T ___ R ___

3. Miscellaneous
 Property in Section

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED

TIME 2:00 pm

MAR 31 1997

DONALD W. KINNUNEN
 REGISTER OF DEEDS
 ALGER COUNTY, MI

Register of Deeds Stamp & File Number

		T.46N. R.21W				F13							
		A	B	C	D	E	F	G	H	I	J	K	L
2	6												
3													
4	7												
5													
6	18												
7													
8	19												
9													
10	30												
11													
12	31												
13													

I, Robert L. Jamros, in a field survey on August 29, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F1: PLS - William A. Burt, DS, 1841, Set quarter Section post * Sugar 26, N.66 E., 13 links * Sugar 10, N.49 W., 33 links **** Herbe L. Fluharty, RLS, 1975. * Set 5/8" x 18" rerod and R.L.S. cap on line proportioned distance at centerline of roads. * P.P., N.70 W., 64.44 feet. * Stop sign, N.22 W., 56.77 feet. * S.E. corner of 18" x 22" conc. slab, S.15 W., 31.43 feet. * Recorded in L.1, P.76, Alger County Records. **** Robert L. Jamros, RLS, 1990. * Alger County Road Commission Project for the rehabilitation of Tunteri Road from Eben-Trenary Road East two miles to the intersection of State Highways M-94 and M-67. * Existing 5/8" rebar monument at this corner position recovered during the centerline alignment and preliminary survey work for this project. Corner position documented on construction plans of Tunteri Road, Alger County. * Not recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F1: Established corner position by standard survey methods and references based on 1990 centerline alignment plans of the Tunteri Road. Corner position lies 0.80 feet North of centerline of Tunteri Road, 8.0 feet East of centerline of gravel road to South and 9.0 feet East of centerline of gravel road to North. Installed monument at corner position and established references. Monumented corner position was established from the best available evidence and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


F1: Set 5/8" x 18" Rebar with a 3 1/4" Aluminum cap no. RBD5325, stamped to identify corner position. * Power Pole, N.61 W., 64.42 feet to PK nail with Aluminum I.D. washer. * Base of 6 foot steel post with "Survey Marker" sign, N.44 1/2 E., 49.27 feet. * Base of 6 foot steel post with "Survey Marker" sign, S.28 E., 46.84 feet. * Base of 6 foot steel post with "Survey Marker" sign, S.50 1/2 W., 61.63 feet. * All bearings are magnetic.

Signed by

Robert L. Jamros

Surveyor's Michigan License No.

25849



Date

25 March, 1997