

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen
Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 17W T 47N R 17W T _____ R _____ T _____ R _____	E1 <u>E13</u> ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____

05-184

TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on April 16, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E1: PLS * William A. Burt, DS, 1841. * Set post corner of Sections 32 and 33 (T47N-R17W). * Fir 12", N.23 E., 14 links. * Sugar 6", N.47 W., 15 links. * Sugar 18", S.70 W., 35 links. * B.Ash 7", S.46 E., 19 links. **** George L. Depew, CS, 1915. * Set iron corner from Government field notes. * No references set. * Recorded in the Minutes of County Surveys, Alger County Records. **** Michigan Department of Conservation, Forestry Division. * Billy D. Buckler, RLS, 1957. * Found 2" pipe with brass cap set by unknown. * Re-witnessed section corner. * 16" Y.Birch (S32 NBT), N.70 W., 47 links. * 13" Elm (S5 NBT), S.07 W., 47 links. * Liber 2, Page 203, Alger County Corner Records. **** Robert L. Jamros, RLS, 1988. * Found 2" iron pipe with brass cap set by Alger County Surveyor, December 1915. * Maple 4", N.66 W., 11.6 feet. * Y.Birch 8", S.03 W., 13.9 feet. * Spruce 12", N.46 E., 14.1 feet. * Liber 3, Page 350, Alger County Corner Records. * No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Located corner search area from previous survey work and standard field survey methods. Found 2" iron pipe with 3 1/4" brass cap correctly stamped, dated December 1915. * Also found 3 reference trees from previous reports in good condition. * Corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E1: Existing 2" iron pipe with 3 1/4" brass cap. * Renewed existing reference trees with BT signs and paint. * Established additional reference tree with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: Maple 5", S.37 E., 7.74 feet, "S4 BT". * Existing - Y.Birch 10", S.01 W., 13.78 feet. * Existing - Maple 5", N.61 W., 11.55 feet. * Existing - Spruce 16", N.47 E., 13.96 feet. * Survey marker sign on 6 foot steel post, S.62 W., 1.5 feet. * All bearings are magnetic.

Signed by *Robert L. Jamros*
Surveyor's Michigan License No. 25849

Date Dec 15 1999

