

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48 NR. 17. W. . .

Alger COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 32, 5  
DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap  
WITNESSES TO CORNER 14" Hard Maple S 35° E 27 links  
Marked 1/4 S NBT  
14" Hard Maple S 42° W 43 1/2 links  
Marked 1/4 S NBT  
Distance measured from brass cap to Notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established by proportionate measure between two Section Corners.

Found squared picket in place.

No evidence of original B.T.s.

Corner established and witnessed October 25, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/8/56  
REGISTERED LAND SURVEYOR