

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 47 NR 17 W

Alger

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 5, 6, 7, 8

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 12" Hard Maple S 28°W 38 links

11" Hard Maple N 6° E 36 1/2 links

8" Hard Maple S 81°E 31 links

Placed location poster on road 2 chains east

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double proportionate measure from good corners.

Section Corner	1 mile	North
Section Corner	2 miles	South
1/4 Corner	1/2 mile	West
1/4 Corner	1/2 mile	East

No evidence of original corner.

Corner established and witnessed October 25, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/8/56  
REGISTERED LAND SURVEYOR