

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48 N.R. 17 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 3-4, T47N R 17W and 33-34 T48N R17W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/30/65 with Miller

WITNESSES TO CORNER..... 8" H. Maple (S3 NBT), S 20° E, 35 Lks.



12" H. Maple (S34 NBT), N 41° E, 26 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on line and the Single Proportioned distance between Section Corners 1 mile to East and West.  
No Original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/9/1965  
REGISTERED LAND SURVEYOR