

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 17 W. --

Alger

----- COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 4, 5, 8, 9.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 15° N. Spruce S 85° W 58 Links to Notch.

10° Balsam N 26° W 75 Links " .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Sec. Cor. by Double Proportionate Measurement to good Corners in all four Directions.

Sec. Cor. one Mile South.
Sec. Cor. one Mile East.
Sec. Cor. one Mile North.
1/4 Cor. 1/4 Mile West.

No evidence of Original Corner.
Cor. lies 1/4 Ch. West of North and South road.

Corner placed and witnessed Sept. 14, 1956.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler.
REGISTERED LAND SURVEYOR

DATE 9/22/56.