

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 17. W. . .

Alger

COUNTY

DESCRIPTION OF CORNER Section Corner to Sections 9, 10, 15, 16. . . . .

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap . . . . .

WITNESSES TO CORNER 12" Hard Maple . . . . . N 31° W . . . . . 33 links . .  
Marked "S 9 NBT"

6" Hard Maple . . . . . N 24° E . . . . . 18 links . .  
Marked "S 10 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

**RESTORED**

Re-established Section Corner by double proportionate measure, from  
Section Corners 1 mile away in all for directions.

No evidence of original corner.

Corner lies in line with road South.

Corner placed and re-established December 18, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 1/7/57  
REGISTERED LAND SURVEYOR