

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 17 W.

Alger COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 26, 27, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 12" Hard Maple S 30° E 19½ links

14" Hard Maple N 62° E 60 links

7" Hard Maple N 40° W 71½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from two Yellow Birches; one stump and one green tree in proper position.

Chainage to good 1/4 Corner 1/2 mile East very good. Several squared trees close. Corner lies in old logging road.

Corner found while checking lines ran by survey crew in this township.

Corner placed and witnessed August 27, 1956.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 9/4/56
REGISTERED LAND SURVEYOR