

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 17 W. .

----- Alger ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 22, 23, 26, 27 . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Hard Maple N 54° E 35 links

9" Hard Maple S 39° E 52½ links

6" Yellow Birch N 69° W 60 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner, found old Cedar post, several old blazes 30-40 years old.

Distance checks north to swamp edge 19.50 chs., south to Section Corner 1 mile, East to Section Corner 1 mile.

No evidence of original witness trees.

Corner found by Forestry Division Survey Crew while making a partial re-survey of this township.

Corner placed and witnessed August 27, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 9/4/56
REGISTERED LAND SURVEYOR