

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47.. NR 17 W. . .

Alger

----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 2, 3, 10, 11. . .

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 14" Hard Maple N 69° E 27 links

14" Hard Maple N 33° W 78 links

7" Hard Maple S 5° W 19 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double proportionate measurement from good corners in four directions.

1/4 Corner	1/2 mile North
Section Corner	1 mile East
Section Corner	1 mile West
Conc. Mon.	1 mile South

No evidence of original corner.

Corner placed and witnessed September 13, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 10/16/56
REGISTERED LAND SURVEYOR