

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 16-17W.

----- Alger ----- COUNTY

DESCRIPTION OF CORNER .. 1/4 Cor. between Secs: 12-7 ..

DESCRIPTION OF CORNER MONUMENT .. 1" Pipe with 4" Brass Cap ..

WITNESSES TO CORNER .. 13" S. Maple (1/4s NBT) S6⁰E 44 Lks. ..

.. 8" H. Maple (1/4s NBT) N3⁰W 45 Lks. ..

.. 9" H. Maple (1/4s NBT) N86⁰W 41 Lks. ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 cor. by prop. measure north and south on twp. line. Several old blazes in vicinity. Cor. lies 30 Lks. west of Woods road. Cor. placed and wit. 9/9/58 with Bill Wallace, Ass't D.F.

SURVEYORS SEAL

SIGNED Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR
DATE 7/28/59