

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 16-17W

Alger

COUNTY

DESCRIPTION OF CORNER Sec. Cor. 13-24-18-19

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" H. Maple (S18 NBT) N61°E 16 Lks.

15" H. Maple (S19 NBT) S45°E 54 Lks.

14" H. Maple (S24 NBT) S76°W 60 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Sec. Cor. on twp. line from cors. 1/2 mile south and 3 miles north. Position fits old blazes north and south. Cor. lies 3/4 chs. east of Trail Road. Cor. wit 9/9/58 with Bill Wallace, Ass't D.F.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR DATE 7/29/59