

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T⁴⁷ NR 17W

Alger COUNTY

DESCRIPTION OF CORNER Sec. Cor. 13-14-23-24

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 18" W. Pine (S13 NBT) N76E 87½ Lks.

9" W. Pine (S14 NBT) N46W 35 Lks.

12" Hemlock (23 NBT) S32W 45½ Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Cor. at wood post as set by unknown surveyor. Found numerous Hemlock Stps. and trees blazed but no positive B.Ts. Position fits well with other Cors. in area. Cor. placed and wit. with Bill Wallace, Ass't D.F. 10/21/58.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 7/27/59
REGISTERED LAND SURVEYOR