

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 47 NR 17W

Alger

COUNTY

DESCRIPTION OF CORNER 1/4 Cor. between Secs. 13-24

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap.

WITNESSES TO CORNER 10" H. Maple (1/4s NBT) S15^oW 24 Lks.

9" H. Maple (1/4S NBT) N73^oW 33 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Cor. from two Beech stps. probable B.Ts. bearing N13E
10 Lks. and S66W 39 Lks. Position is 1 link south and 1 link west
of a point midway and on line between two Sec. Cors. Cor. placed
and Wit. 10/21/58 with Bill Wallace, Ass't D.F.
Squared and scribed 8" Beech at Cor.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 7/27/59
REGISTERED LAND SURVEYOR