

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 47-48 NR 17W

----- Alger ----- COUNTY

DESCRIPTION OF CORNER ----- Sec. Cor. 1-2-35-36 -----

DESCRIPTION OF CORNER MONUMENT ----- 5' Iron Fence Post -----

WITNESSES TO CORNER ----- 7" Y. Birch (S35 NBT) N16W 26 Lks. -----

----- 8" H. Maple (S36 NBT) N59E 8 Lks. -----

----- 8" H. Maple (S 1 NBT) S30E 44 Lks. -----

----- 7" H. Maple (S 2 NBT) S40W 26 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-witnessed Cor. as set by unknown surveyor. Found no evidence of original witnesses. Found severed blazed trees and a line of blazes to East. Position fits well with Cors. 1 mile South, East and West. Cor. lies 3 chs. West of Woods Road. Cor. wit. 9/16/58 with Bill Wallace, Ass't D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED ----- Billy D. Buckler ----- DATE 7/27/59
REGISTERED LAND SURVEYOR