

✓

**MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION**

LAND CORNER RECORD

T. 47 N.R. 17 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 28-29-32-33

CORNER MONUMENT 1 1/2" x 30" Iron Pipe buried 8" in approximate C/L of dirt road

DATE MONUMENT PLACED AND WITNESSED 6/10/65 Bray and Miller

WITNESSES TO CORNER..... 12" Elm (S33 NBT), S 29° E, 102 1/2 Lks.



14" H. Maple (S32 NBT), S 73° W, 48 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from probable BT (Sugar 16" N 74° W 32 Lks) which is a rotted stump with axe marks and overgrowth.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/10/1965
REGISTERED LAND SURVEYOR