

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 NR. 17W

Alger COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs: 21-22-27-28

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 5" Cedar (S27 NBT) S13⁰E 33 1/2 Lks.

13" W. Pine (S21 NBT) N55⁰W 80 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from two original B.Ts. (probable). Cedar, down, bearing S43⁰W 19 Lks. old blazes. Could find no scribe marks. Y. Birch stump bottom N43⁰E 3 Lks. Position fits well with other cors. in area. Found by Forestry Division Survey Crew. Cor. placed and wit. 9/17/58 with Bill Wallace, Ass't D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 7/29/59
REGISTERED LAND SURVEYOR