

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48 N.R. 17 W


Alger COUNTY

DESCRIPTION OF CORNER East 1/16 Corner for Secs. 3, T47N R17W, 34 T48N R17W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/30/65 with Miller

WITNESSES TO CORNER..... 19" Cedar (E1/16 BT), N 31° E, 42 Lks.



5" H. Maple (E1/16 BT), S 07° W, 16 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set midway and on Line between 1/4 Corner to West and Section Corner to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/9/1965
REGISTERED LAND SURVEYOR