

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 17 & 18 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 25/36 T47N R18W & 30/31 T47N R17W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/8/65 Bray & Miller

WITNESSES TO CORNER..... 9" H. Maple (S25 NBT) N 40° W, 24½ Lks.



8" H. Maple (S31 NBT) S 64° E, 41½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single proportioned measurement between Section Corners, 1 mile to South and 3 miles to North.
No original evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/9/1965
REGISTERED LAND SURVEYOR