

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 17 & 18 W


Alger COUNTY

DESCRIPTION OF CORNER Section Corner for Secs., 24-25 T47N R18W & 19-30 T47N R17W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/8/1965 Bray and Miller

WITNESSES TO CORNER..... 9" Elm (S25 NBT), S 79° W, 93½ lks.



7" Elm (S30 NBT), S 34° E, 78½ lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was reestablished by single proportioned measurement between Section Corners 1 mile to South and 2 miles to North.  
No original evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/9/1965  
REGISTERED LAND SURVEYOR