

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 47... NR 17W...

----- Alger ----- COUNTY

DESCRIPTION OF CORNER 1/4 Cor. between Secs. 23-24 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap. -----

WITNESSES TO CORNER 12" W. Pine (1/2" NBT) N74E 42 1/2 Lks. -----

9" Y. Birch (1/2" NBT) N50W 60 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Cor. from one Hemlock B.T. bearing S58°E, 21 Lks.
B.T. is a stump which has been cut. Found notch and part of
blaze in place. Position fits Cors. North & South. Cor.
placed and wit. with Bill Wallace, Ass't D.F. 10/21/58.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 7/27/59
REGISTERED LAND SURVEYOR