

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Alger

(County)

Located In:

Corner Code #:

- |                                    |                           |           |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey              | T <u>47N</u> R <u>17W</u> | <u>67</u> |
|                                    | T <u>47N</u> R <u>17W</u> | <u>66</u> |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Sep 18 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (67) Corner common to Sections 15-16-21-22. 1956: Billy D. Buckler found and accepted a 2" pipe with brass cap set by unknwn surveyor at record bearing and distance from possible Hard Maple BT remains. 9" Hard Maple N60W 22 links, 12" Hard Maple N15E 30 links.
- (66) Quarter corner common to Sections 15-16. 1956: Billy D. Buckler, RLS found and accepted a 2" pipe with brass cap set by unknown surveyor. 9" Hard Maple S68W 29 links, 6" Hard Maple N63E 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (67) Recovered a 2" iron pipe capped with a 2" dia. brass tablet stamped to identify the corner, in good condition, and at substantial record bearing and distance from the 1956 NBTs, both green. I note that the bearings to these two trees have been transposed in the 1956 record. Accept same as the best available evidence of the position of the original corner.
- (66) Recovered a 2" dia. iron pipe capped with a 2" dia. brass tablet stamped to identify the corner, in good condition, at record bearing and distance from the 1956 NBTs, both in good condition. Accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(67) Found 2" iron pipe with 2" brass cap. Blazed, scribed, and set measuring nails in:

- |                       |       |
|-----------------------|-------|
| 16" Sugar N55W 19.95' | "S16" |
| 14" Sugar N19E 14.7'  | "S15" |
| 5" Beech S28E 8.7'    | "S22" |
| 6" Beech N65E 5.1'    | "S15" |

Set cedar post adjacent. Bearings are magnetic. Distances to nail with disc.

(66) Found 2" pipe with brass cap. Blazed, scribed, and set measuring nails in the following:

- |                       |            |
|-----------------------|------------|
| 14" Sugar S70W 19.25' | "1/4S"     |
| 12" Sugar N64E 24.85' | "1/4S"     |
| 8" Maple N14E 13.4'   | "1/4S NBT" |
| 6" Sugar S13W 16.1'   | "1/4S NBT" |

Bearings are magnetic. Distances are to nail with disc.



Signed by Stephan J. Szyszkoski Date 10/17/01

Surveyor's Michigan License No. 33986  
 For the Michigan Department of Natural Resources - Office of Property Management