

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Alger  
 (County)

|                                    |                           |                |
|------------------------------------|---------------------------|----------------|
|                                    | Located In:               | Corner Code ## |
| 1. Public Land Survey              | T <u>47N</u> R <u>17W</u> | <u>H5</u>      |
|                                    | T <u>47N</u> R <u>17W</u> | <u>H7</u>      |
|                                    | T _____ R _____           | _____          |
|                                    | T _____ R _____           | _____          |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____          |
|                                    | S _____ T _____ R _____   | _____          |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____          |
|                                    | S _____ T _____ R _____   | _____          |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

H7 Oct 03 2001  
 H5 Sep 24 2001

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    | ● |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    | ● |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(H5) Quarter corner common to Sections 10-15. Original corner reestablished in 1958 by Billy D. Buckler RLS, midway and on line between two section corners. 1" pipe with 4" brass cap. 6" H. Maple twin N10E 60.5 links, 12" Elm S80W 90 links.  
 (H7) Quarter corner common to Sections 15-22. Corner previously re-witnessed in 1956 by Billy D. Buckler, RLS. Found Concrete monument with 1/2" steel bar set by unknown surveyor. 8" Elm N65E 16 links, 6" Hard Maple S79W 26 links. Corner described on recorded survey by William R. Donnan, 1974: Found Conc. Mon. 10" Elm 10.90' N55E, 6" Elm 9.29' N05W, 7" Maple 4.59' S65W. Described on 1978 recorded survey by R.L. Jamros: Fd. Conc. Mon. Maple 6" S70E 9.92', Elm 8" N65E 10.90', T. Elm 4"-6" N4W 9.25', Maple 6" S56W 4.54'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(H5) The 1956 monument was not recovered. Found the remains of the H. Maple NBT, a rotting Sugar with a younger 5" Maple growing from it. The stump bottom of the NBT Elm was recovered. No markings or measuring notch visible on either. Re-monumented the corner midway and on a line of mean true bearing between section corners 2644.34' east and west, the position also in accord with the record bearings and distances to the remains of the 1956 bearing trees.  
 (H7) Recovered a 1/2" iron rod encased in a 4"x4" concrete monument, in accord with the dimensions stated on the above referenced surveys, and at record bearing and distance from the 1956 NBT Hard Maple SW and the 1978 NBT Maple SW. Accepted the monument as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

|  |   |
|--|---|
| (H5) Set 1" IDx36" iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in: | (H7) Found 1/2" iron rod encased in a 4" square concrete monument. Blazed, scribed, and set measuring nails in: |
| 5" Maple N15E 39.6' "1/4S NBT"   | 12" Sugar S85W 17.1' "1/4S"   |
| 6" Twin Maple S61E 25.05' do   | 6" Maple S55W 4.35' "1/4S NBT"  |
| 10" Maple S22W 23.0' do  | 6" Maple N54W 20.5' do  |
| 8" Maple Nest 52.85' do  | 6" Maple N26W 6.25' do  |
| Bearings are magnetic. Distances to nail with disc.  | Set 4" squared and scribed post adjacent. Bearings are magnetic. Distances to nail with disc.                   |



Signed by Stephan J. Szyszkoski Date 10/17/01