

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alger

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|-----------|
| 1. Public Land Survey | T <u>47N</u> R <u>17W</u> | <u>H6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>15</u> T <u>47N</u> R <u>17W</u> | <u>9</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 24 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


- (H6) Center of Section 15. Corner not established in the original survey.
 (9-Sec. 15) East 1/16 corner, Section 15. Corner not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (H6) Established the corner at the intersection of straight lines connecting opposite Quarter corners.
 (9-Sec. 15) Established the corner midway and on a straight line between Center of Section 1321.69' west and Quarter corner 1321.69' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (H6) Set 1"IDx36" iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in: | (9) Set 1"IDx36" iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in: |
| 12" clump Maples S29W 9.6' "CS BT" | 5" W. Birch N08E 6.7' "E1/16 BT" |
| 12" Twin W. Birch S61E 14.2' do | 10" Maple N77W 22.8' do |
| 14" clump Maples N52W 32.05' do | 8" Maple S54W 18.35' do |
| 12" Maple N18E 23.4' do | 6" W. Birch S20E 24.1' do |
- Bearings are magnetic. Distances to nail with disc.



Signed by Stephan J. Szyszkoski Date 10/17/01
 Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources - Office of Property Management