

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>47N</u> R <u>17W</u>	<u>E6</u>
	T <u>47N</u> R <u>17W</u>	<u>E7</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 08 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (E6) Quarter corner common to Sections 16 and 17. 1965 - Corner recovered and re-witnessed by F.J. Bray RLS: "This corner was set by unknown Surveyor. 1 1/4" Iron pipe with 3" brass cap. Witnesses: 12" H. Maple S86W 18 links, 11" H. Maple S79E 42 links.
- (E7) Corner common to Sections 16-17-20-21. 1956 - Recovered and recorded by Billy D. Buckler RLS: "One Cedar B.T. in excellent condition". Found 2" gal. Iron pipe with brass cap. Witnesses: 14" White Pine N51W 41.5 links, 9" Cedar S24W 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (E6) Recovered a 2" O.D. iron pipe with 3" brass cap at record bearing and distance from the 1960 witnesses, both in good condition. Accepted same as the best available evidence of the position of the corner.
- (E7) Found a 2" O.D. Iron pipe with 3" brass cap in good condition and at record bearing and distance from the 1956 W. Pine NBT NW, in good condition with old blaze. There appears to be an error in the 1956 record describing the 9" Cedar SW. No tree was recovered at that position. However, a blazed cedar was found at about 14.5' (22 links) from the corner at the same bearing as the W. Pine NBT, and a second marked cedar was found at N18W 11.4' distant, with open blaze facing the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (E6) Fd. 2"OD Iron pipe with 3" brass cap. Set measuring nails in:<br>16" Sugar N24W 15.3' mrkd "1/4S NBT"<br>16" Sugar S18W 28.13' do<br>17" Sugar West 12.68' mrkd "1/4S" *<br>18" Sugar S74E 28.4' do *<br>Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT. | (E7) Fd. 2"OD Iron pipe with 3" brass cap. Set measuring nails in:<br>10" Hemlock S39E 35.0' mrkd "S21 NBT"<br>7" Balsam S46W 16.9' "S20 NBT"<br>17" Cedar N18W 11.4' open upper blaze<br>27" W. Pine N44W 26.9' mrkd "S17" *<br>Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBT. |
|--|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/12/06