

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>17W</u>	F5
	T <u>47N</u> R <u>17W</u>	F7
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

F7 Aug 08 2006
 F5 Aug 01 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5						●							
6	18		17			16		15		14		13	
7						●							
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F5) Quarter corner common to Sections 9 and 16. 1956 - Corner recovered and re-witnessed by Billy D. Buckler RLS: Found 2" pipe with brass cap set by unknown surveyor. One Hard Maple "probable B.T." in proper position. Witnesses: 10" Hard Maple S68E 18 links, 12" Hard Maple N20W 50.5 links.
 (F7) Quarter corner common to Sections 16 and 21. 1960 - recovered and re-witnessed by Billy D. Buckler RLS: Found 2" iron pipe with 3" brass cap. Witnesses: 6" Soft Maple N78W 22.5 links, 10" Elm N35E 34 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F5) Recovered a 2" O.D. iron pipe with 3" brass cap at record bearing and distance from the 1956 witnesses. The Hard Maple SE is partially uprooted, the Hard Maple NW is in good condition. Recovered the probable OBT noted in the 1956 record, a Sugar stump S78W 16.5' distant, no markings visible. Left the monument in place and made new witnesses.
 (F7) Found a 2" O.D. iron pipe with 3" brass cap in accord with the 1960 witnesses of record. The Elm NE is now a stump. The Soft Maple NW is in good condition. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F5) Found 2"OD iron pipe with 3" brass cap. Set measuring nails in: 8" Sugar N86E 21.25' mrkd "1/4S NBT" 11" Sugar N56E 21.15' do 18" Sugar S23W 16.85' do 15" Sugar N15W 33.8' mrkd "1/4S" * Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBT.	(F7) Fd. 2"OD I.pipe with 3" brass cap. Set measuring nails in: 8" Maple S55W 19.8' mrkd "1/4S NBT" 6" Maple N44E 26.8' do 12" Maple S55E 24.17' do 10" twin Maple N76W 15.2' "1/4S" * Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/12/06