

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S 16 T 47N R 17W	1/64 west of G5
	S 16 T 47N R 17W	1/64 west of G6
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Aug 08 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(1/64 corner west of G5) The E-E 1/64 corner between Sections 9 and 16, being the NE corner of the W1/2 of the NE1/4 of the NE1/4 of Section 16. Not established in the original survey.  
 (1/64 west of G6) C-E-E 1/64 corner, Section 16, being the SE corner of the W1/2 of the SE1/4 of the NE1/4 of Section 16. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(1/64) Established the corner midway and on the Section line between corner G5 660.29' east and 1/16 corner #2 660.29' west. The position for the corner falls about 50' south of C/L of road.  
 (1/64) Established the corner midway and on a straight line between Quarter corner G6 664.48' east and 1/16 corner #9 664.48' west. The position for the corner falls in a beaver pond.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(1/64) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Maple S26W 6.75' mrkd "1/64 BT" 5" Y. Birch N65W 2.35' do 11" Maple S55E 13.42' do 7" Spruce N71E 10.25' do An iron fence post bears S24W, 11.75' distant. Bearings are magnetic. Distances to trees are to nail with tag.	(1/64) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in the following trees (all standing dead): 16" Cedar S06W 34.0' mrkd "1/64 BT" 12" Cedar S33W 34.52' do 16" Cedar S50W 38.2' do 16" Cedar S76W 39.95' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/12/06