

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|---------------------------------------|---------------|
| <u>Alger</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 2. Property Controlling in Section | S <u>16</u> T <u>47N</u> R <u>17W</u> | <u>3</u> |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File
Number

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

Aug 08 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(3-Sec. 16) North 1/16 corner between Sections 16 and 17. 1965 - Established by Frank J. Bray RLS midway and on line between 1/4 corner to South and Section corner to North. Set 1" I.pipe with 4" aluminum cap. 12" Cedar S22E 17 links, 10" Cedar N24E 19.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 16) Found the 1965 monument in good condition, at the record position, and at record bearing and distance from the 1965 BTs, both in good condition. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 17" Cedar S20E 11.8' old blazes *
 16" Cedar N30E 13.4' do *
 14" Cedar S74E 26.9' mrkd "N1/16 BT"
 13" Ash N25W 7.4' do
 Bearings are magnetic. Distances are to nail with tag. * denotes 1965 BT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/12/06

For the Michigan Department of Natural Resources, Office of Land and Facilities