

# SURVEY & REMONUMENTATION

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 5/8 1996

JUL 30 1996

4-384

Donald W. Carlson  
Chairman

## LAND CORNER RECORDATION CERTIFICATE COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alger Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

FILED  
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- |                                      |   |            |   |            |             |
|--------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey                | T | <u>46N</u> | R | <u>18W</u> | <u>E1</u>   |
|                                      | T | <u>47</u>  | R | <u>18</u>  | <u>E-13</u> |
|                                      | T | _____      | R | _____      | _____       |
|                                      | T | _____      | R | _____      | _____       |
| 2. Property Controlling In Section   | S | _____      | T | _____      | _____       |
|                                      | S | _____      | T | _____      | _____       |
| 3. Miscellaneous Property in Section | S | _____      | T | _____      | _____       |
|                                      | S | _____      | T | _____      | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Robert L. Jamros, in a field survey on February 09, 1996, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E1: PLS-William A. Burt, DS, 1841, Set post corner of sections 4 & 5 - Sugar 12", N.37 E., 11 links, Birch 6", N.38 W., 36 links.\*\*\*\*\* Walter W. Gleason, Deputy CS, 1912, Iron corner set by intersection of the lines from the S1/4 corner and the E1/4 corner continued. Old surveyors plug found at this point. Lines run by compass.\*\*\*\*\* Alger County Road Commission, George Depew, 1915, County Surveyor, Corner shown as brass cap iron on road plans for the Grand Marais-Munising Road. No references given.\*\*\*\*\* Michigan State Highway Department, Project No. 02022, Highway Plans for M-94, 1958, Corner position shown as pipe with brass cap lying 1.81 feet South of survey centerline. References as follows - P.Pole, S.28 W., 32.25 feet, Tele. Pole, N.38 E., 40.33 feet, P.Pole, N.12 W., 94.65 feet.\*\*\*\*\* Herbert L. Fluharty, RLS, 1977, Found 1" iron bar in monument box on centerline blacktop road and centerline blacktop road to the north. Established the following references, P.Pole, N.13 W., 92.26 feet, P.Pole, N.58 E., 59.09 feet, P.Pole, S.40 W., 33.43 feet. Filing No. 89, Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E1: Found 1" iron bar in monument box on centerline of asphalt road, County Highway H-58 East (old M-94), at centerline of asphalt road to North. Found two existing references (NW and SW) of the 1977 report. Upgraded existing references to current Alger County Standards and established additional references. Corner position has been verified against existing corners East and West. Monument position is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E1: Set in place of 1" Bar a 5/8"x 18" rebar with Berntsen 3 1/4" aluminum cap no. RBD5325, stamped to identify corner position. Established the following references. N.E. corner of East concrete headwall of culvert, road North, N.31 E., 45.53 feet.\*\* N.W. corner of West concrete headwall of culvert, road North, N.22 W., 45.48 feet.\*\* Exist. BT, P.Pole, scribed BT at base and installed PK nail with aluminum I.D. washer for measure, N.09 W., 92.36 feet.\*\* Exist. BT, P.Pole, scribed BT at base and installed PK nail with aluminum I.D. washer for measure, S.45 W., 33.50 feet.\*\* All bearings are magnetic.



Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12 1996