

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

ALGER

(County)

Located In:

Corner Code #/

1	Public Land Survey		T	R		
			T	R		
			T	R		
			T	R		
2	Property Controlling in Section	S 29	T 47N	R 19W	1	
		S 29	T 47N	R 19W	3	
3	Miscellaneous Property in Sec.	S	T	R		
		S	T	R		
4	Lot No					Recorded Plat
5	Private Claims					

Register of Deeds Stamp & File Number

I, **Gerald L. Wiggins** in a field survey on 1-31 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

- West 1/16 Corner on North side of Section 29. Not previously set.
- North 1/16 Corner on West side of Section 29. Not previously set.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Corner set due east and record distance, 1320' from the N.W. Corner of Section 29.
- Corner set midpoint on line between West 1/4 Corner and N.W. Section Corner of Section 29.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe with plastic R.L.S. Cap set at both corners.

- |   |                         |   |                           |
|---|-------------------------|---|---------------------------|
| 1 | 10" Maple, N56°W, 16.5' | 3 | 14" W. Pine, S61°W, 6.85' |
|   | 4" Maple, N28°W, 15.3'  |   | 10" W. Pine, N85°W, 4.15' |
|   | 10" Maple, East, 23.3'  |   | 10" Balsam, S63°E, 2.55'  |
|   | 8" Maple, South, 28.1'  |   | 8" Spruce, S15°W, 4.2'    |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Gerald L. Wiggins  
 Gerald L. Wiggins  
 Surveyor's Michigan License No. 23521

Date 6-25-91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

