

Donald W. Kinnunen
 Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-311

For corners in

Alger
 (County)

Located In:

Corner Code #

FILED
 E 9:00 a.m.

- | | | |
|------------------------------------|---------------------------|------------------------|
| 1. Public Land Survey | T <u>47N</u> R <u>22W</u> | <u>B11</u> |
| | T _____ R _____ | <u>SURVEY &</u> |
| | T _____ R _____ | <u>REMONUMENTATION</u> |
| | T _____ R _____ | <u>MAY 10 1995</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | <u>COMMISSION</u> |

APR 20 1995

DONALD W. KINNUNEN
 EG

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. James, in a field survey on October 25, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11		●											
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B11: PLS-Alfred Millard, DS, 1852, Set Qr. Section Post- Beech 6", N.32 W., 4 links, Beech 10", S.38 E., 33 links. CCI Forestry Division, Land and Timber Examination Report, D.B. Whittier, 1950, indicates Beech 12" and Beech 14" stub at corner location 37.95 chains (GLO) from west township line., No references given., R.Radcliffe, RLS, 1962, indicates a post at corner position. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B11: Found 5 ft. steel fence post at corner position. From corner position found 18" Beech (alive) with blaze scar and scibing hollowed out, GLO BT, N.32 W., 4 links, Beech 6". All that remains of BT stub is a stump hole of decayed unidentifiable wood. Replaced existing steel post with new monument. Found old blaze lines east and west. Found two existing BT's not of record and established additional reference trees. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. cap stamped to identify corner position. Renewed existing reference trees w/BT signs and paint. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Hemlock 34", N.02 E., 5.51 feet, "Face Blz's", Ex. Hemlock 13", S.57 W., 17.09 feet, "Crown Blaze w/ Notch", Hemlock 14", S.48 E., 39.87 feet, "1/4s BT", Hemlock 7", N.48 E., 34.69 feet, "1/4s BT", Steel witness post with Survey marker sign, S.80 E., 3.3 feet. All bearings are magnetic.

Signed by

Robert L. James
 25849

Date 12 April, 1995

Surveyor's Michigan License No.