

Approved by Aiger County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of  
 P.A. of 1990 On 9/7 1994

4-270

Mr. Davis  
 ACTING Chairman  
 For corners in

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED  
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>C4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	●	8	9	10	11	12					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on July 21, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C4: P.L.S., Alfred Millard, OS, 1852. Set quarter section post. Cedar 10, N.45 W., 31 links. Hemlock 10, S.35 E., 18 links. C.C.I. Co., Forestry Records, Land & Timber Examination Reports, 1940 thru present. Reports indicate, Hemlock BT, 2" stake and Cedar register tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C4: Ran north on a corrected compass line from section corner to south on G.L.O. Bearing Found Maple line tree w/scars of chop marks still visible, 1.0 feet west of compass line, at G.L.O. call of 30.55 chains. At 40.0 chains found 5/8" rebar w/R.L.S. cap no. 24589 7.0 feet west of line, and evidence of four new reference BT's. At 40.16 chains on line found record Cedar register tree. A search was made at the original BT locations for remaining evidence of Cedar and Hemlock. Remains of Hemlock roots were found at S.35 E., 12.0 feet (18.18 links). Accepted existing 5/8" rebar as corner position. Installed new monument over exist. rebar. Maple line tree and Hemlock remains fit corner position well and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4: Set 2 1/4" x 30" Alum. Mon. w/3 1/4" Alum. cap stamped to I.D. Corner. Renewed existing and est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Cedar 16", N.10 E., 25.52 feet, "BT". Ex. Hemlock 9", S.75 E., 28.45 feet, "BT". Ex. Maple 11", S.19 W., 19.20 feet, "BT". Maple 7", N.29 W., 15.30 feet, "BT". Survey Marker Post, S.20 E., 1.5 feet.

Signed by Robert L. Jamros Date 10 July, 1994

Surveyor's Michigan License No. 25849