

Approved by Alger County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of  
 P.A. of 1990 On 9/7 1994

Mc Davis  
 ACTING Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

4-269

For corners in

Alger

(County)

Located In:

Corner Code #

- |                                    |   |            |   |            |           |
|------------------------------------|---|------------|---|------------|-----------|
| 1. Public Land Survey              | T | <u>47N</u> | R | <u>22W</u> | <u>C5</u> |
|                                    | T | _____      | R | _____      | _____     |
|                                    | T | _____      | R | _____      | _____     |
|                                    | T | _____      | R | _____      | _____     |
| 2. Property Controlling in Section | S | _____      | T | _____      | R         |
|                                    | S | _____      | T | _____      | R         |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | R         |
|                                    | S | _____      | T | _____      | R         |

FILED  
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert L. Janros, in a field survey on June 26, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

C5: P.L.S., Alfred Millard, DS, 1852. Set post corner fo Sections 7, 8, 17 & 18. Maple 8, N.30 W., 22 links. Hemlock 18, S.28 E., 32 links. C.C.I. Co. Forestry Records, Land & Timber Examination Reports, 1940 thru present. Reports indicate a 4" post, no references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C5: Found 4" Cedar post and 5/8" rebar w/R.L.S. cap no. 24589, approx. 60 feet NEly of woods road. Found four exist. reference BT's. A search was made at the original BT locations for Maple and Hemlock, only depressions in ground found, evidence inconclusive. G.L.O. line tree 30.55 chains north was found and supports this corner position. Installed new monument over existing rebar. Evidence of corners 40.0 chains east and 40.0 chains north support this corner position and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C5: Set 2 1/4" x 30 Alum. Mon. W/3 1/4" Alum. cap stamped to I.D. corner. Renewed existing reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Hemlock 16", N.60 E., 18.52 feet, "BT". Ex., Fir 8", S.01 E., 15.50 feet, "BT". Ex. Maple 14", N.55 W., 32.91 feet, "BT". Ex. Maple 12", N.13 W., 37.16 feet, "BT". Survey Marker Signs, N.69 E., 1.5 feet.

Signed by Robert L. Janros  
 Surveyor's Michigan License No. 25849

Date 10 July, 1994