

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 9/9 1994

Mc Davis
ACTING Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-268

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>C6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. James, in a field survey on August 14, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C6: P.L.S., Alfred Millard, DS, 1852. Set quarter section post. Hemlock 20, N.68 E., 31 links. Hemlock 24, S.42 W., 45 links. C.C.I. Co. Forestry Records, Land & Timber Examination Reports, 1940 thru present. Reports indicate 4" Hemlock stake and BT Hemlock stub. Michigan Dept. of Conservation, Frank J. Bray, R.L.S., October 1973. This corner was replaced from point of old wood post which is in the proper distant and bearing from original BT (Hemlock stump with scribe marks on lower face) to the S.W. set 1" Iron pipe with 4" alum. cap, Est. references, 16' Cedar, N.88 E., 33.6 feet, 14" Hemlock, S.71 W., 38.0 feet. Recorded in filing no. 32, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C6: Found 1 1/4" G.I.P. w/4" Alum. cap (M.D. of C.) identified by references on recorded report, and 4" Hemlock stake w/Sq'd top scr'd 1/4". Corner lies in open mixed timber on Ely side small ridge. Found remains of Gov't BT, Hemlock in S.42 W., 45 links position. Accepted exist. monument and renewed existing and established new reference trees. Corner position was established from Gov't Hemlock BT and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C6: 1 1/4" G.I.P. w/4" Alum. cap (found), M.D. of C., stamped to I.D. corner. Renewed existing and est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers. Maple 7", S.24 E., 14.85 feet, 1/4S-BT. Ex. Hemlock 26", S.70 W., 38.37 feet. Ex. Cedar 20", N.88 E., 34.18 feet, 1/4S-NBT. Hemlock 12", N.33 W., 54.53 feet, 1/4S-BT. Survey Marker Post, S.05 E., 1.2 feet

Signed by Robert L. James Date 10 July, 1994
Surveyor's Michigan License No. 25849