

Donald W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-304

For corners in

<u>Alger</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>C7</u>
	T _____ R _____	SURVEY &
	T _____ R _____	REMONUMENTATION
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>MAY 10 1995</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	COMMISSION

FILED
 E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
 EG

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Jamros, in a field survey on November 30, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C7: PLS-Alfred Millard, DS, 1852, Set post corner of sections 17,18,19 and 20, - Hemlock 12", S.38 E., 28 links, Hemlock 30", S.58 E., 25 links., CCI Forestry Division, Land Corner Record No. 987, Robin D. Steinhoff, 1967, Found 4' hemlock post believed to be section corner. New Witnesses: Maple 8", S.27 E., 28 links, Hemlock 3", N.64 W., 5 1/2 links. Frank J. Bray, RLS, 1973, Established corner by double proportionate measurement. New witnesses: 9" Hemlock, S.40 E., 18.9 ft., 4" W.Pine, N.38 W., 21.5 ft., Filing No. 32, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C7: Found 1 1/4" G.I.P. with 4" Alum. cap marked to identify corner position. Found decayed post lying on ground by monument. A search was made for original BT's at BT locations, results inconclusive. 1973 report, Filing no. 32 A.C.Records stated corner position was established by double proportionate measurement. Found BT's of 1973 report in excellent condition. Established additional reference BT's. Corner position lies on young Pine ridge in dense mixed timber. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C7: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Firmed monument up by piling rocks around the base of the monument. Renewed existing reference trees w/ BT signs and paint. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure in all reference trees w/ brass I.D. washers. Ex. Hemlock 14", S.35 E., 19.53 feet, "S20 NBT", Ex. Hemlock 9", S.20 W., 24.50 feet, "NBT", Ex. W.Pine 16", N.36 W., 21.57 feet, "S18 NBT", Hemlock 12", N.62 1/2E., 44.31 feet, "S17 BT", Steel witness post with Survey marker sign, S.29 W., 2.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
 Surveyor's Michigan License No. 25849

Date 12 April, 1995