

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-306

For corners in
Alger

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------------------|
| 1. Public Land Survey | T <u>47N</u> R <u>22W</u> | <u>C8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | <u>SURVEY &</u> |
| | T _____ R _____ | <u>REMONUMENTATION</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | <u>MAY 10 1995</u> |
| | S _____ T _____ R _____ | <u>COMMISSION</u> |

FILED
E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
EG

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Janros, in a field survey on December 01, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C8: PLS-Alfred Millard, DS, 1852, Set Qr. Section Post, Spruce 6", N.58 E., 33 links, Spruce 6", S.68 W., 60 links. No Subsequent Restoration. Frank J. Bray, RLS, 1973, This corner was set mid-point on line between section corners North and South. New witnesses: 10" W.Pine, S.43 E., 25.3 ft., 18" W.Pine, N.83 E., 31.0 ft. Filing No. 36, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C8: Found 1 1/4" G.I.P. with 4" Alum. cap marked to identify corner position and squared 3" post. A search was made for original BT's at GLO BT locations with no results. Corner was reestablished by single proportionate measurement as stated in report by Frank J. Bray, 1973. Found BT's of 1973 report in excellent condition. Established additional reference trees. Corner lies in open, dry marsh of mixed conifer. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C8: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Firmed up monument by driving deeper into ground. Renewed existing reference trees w/ BT Signs and paint. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails w/ brass I.D. washers for measure in all of the following reference trees. Ex. W.Pine 24", S.41 E., 31.87 feet, "1/4s BT", Ex. W.Pine 18", N.85 E., 25.66 feet, "NBT", W.Pine 16", N.51 W., 23.66 feet, "1/4s BT", W.Pine 14", S.40 W., 54.82 feet, "1/4s BT", Steel witness post with Survey marker sign, N.28 W., 1.9 feet. All bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by _____

Robert L. Janros

Date _____

12 April, 1995

Surveyor's Michigan License No. _____

25849