

Approved by Alger County  
 Survey Registration Commission  
 Michigan Public Act 345 of  
 1970 On 4-8-1995

Donald W. Carlson  
 Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

4-307

For corners in  
Alger  
 (County)

Located In: Corner Code #

FILED  
E 9:00 a.m.

- 1. Public Land Survey T 47N R 22W C9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**  
MAY 10 1995  
**COMMISSION**

APR 20 1995

DONALD W. KINNUNEN  
 EG

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on December 05, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C9: PLS-Alfred Millard, DS, 1852, Set post corner of sections 19,20,29 and 30, - Hemlock 18", N.65 W., 28 links, Hemlock 18", S.60 E., 10 links. CCI Forestry Division, Land and Timber Examination Report, R.Radcliffe, RLS, 1950 through 1962, indicates post at corner position. Frank J. Bray, RLS, 1973, This corner was set from two hemlock stump bottoms. New witnesses: 6" Cedar, N.50 W., 23.5 ft., 9" Hemlock, S.35 E., 20.9 ft. Filing No. 34 Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C9: Found 1 1/4" G.I.P. with Alum. cap marked to identify corner position and squared 4" post. A search was made for original BT's at 6L0 BT locations. Found decayed remains of Hemlock at both locations. Corner position set from original BT Hemlock stump bottoms as reported by Frank J. Bray, 1973 and established new BT's. Found new BT's in good condition and established additional reference trees. Corner lies on northerly edge of small pot hole in mixed timber. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C9: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Renewed existing reference trees w/ BT signs and paint. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails w/ brass I.D. washers in all of the following reference trees. Ex. Cedar 8", N.50 W., 23.69 feet, "S19 BT", Ex. Hemlock 11", S.32 E., 20.80 feet, "S29 BT", Hemlock 20", N.36 E., 50.15 feet, "S20 BT", Hemlock 8", S.45 W., 23.41 feet, "S30 BT", Steel witness post with Survey marker sign., S.49 W., 1.5 feet. All bearings are magnetic.

Signed by Robert L. Jamros  
 Surveyor's Michigan License No. 25849

Date 12 April, 1995