

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 4-8-1995

Michael W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-313

For corners in
 Alger

(County)

Located In:

Corner Code #

FILED

E 9:00 a.m.

1. Public Land Survey T 47N R 22W C12

T R

T R

T R

T R

**SURVEY &
 REMONUMENTATION**

APR 20 1995

DONALD W. KINNUNEN
 EC

2. Property Controlling S T R

in Section S T R

3. Miscellaneous S T R

Property in Sec. S T R

MAY 10 1995

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Janros, in a field survey on October 25, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C12: PLS-Alfred Millard, DS, 1852, Set Or. Section Post- Cedar 12", N.22 E., 17 links, Cedar 10", S.48 W., 20 links. CCI Forestry Division, Land Corner Record Page No. 257, R.J. Brotherton, RLS, 1948, Set 3" peeled cedar post from original cedar BT's. New references: Maple 8", S.20 E., 38 links, Hemlock 5", N.28 W., 30 links. Corner is on a 10 foot high hemlock ridge south of swamp.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C12: Found 4" Cedar post and downed 3" Cedar post. Found original BT (stub) with scribing still visible in southwest location and original BT (decayed) down in northeast location. Found post and new BT's, Hemlock 5, in good condition and Maple 8, (decayed stump) of report of R.J. Brotherton, 1948. Old blaze lines to north and south. Corner lies on small ridge at southerly edge of thick, low, swampy area. Replaced post with new monument and established additional reference trees. Existing corner monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C12: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Renewed existing reference trees w/ BT signs and paint. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Hemlock 14", N.26 W., 19.90 feet, "Crown Blz", Hemlock 6", S.51 W., 33.80 feet, "1/4s BT", Hemlock 14", S.38 E., 41.23 feet, "1/4s BT", Y. Birch 10", N.69 E., 47.37 feet, "1/4s BT", Steel witness post with Survey marker sign, N.31 E., 1.5 feet. All bearings are magnetic.

Signed by Robert L. Janros

Date 12 April, 1995

Surveyor's Michigan License No. 25849